BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16544

APPROVED SCHEDULE - B

No.EE.[redacted]TP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Construction of Additional floor for AEE Offices in ward No 7 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K.V. Subbareddy	
				In Figures	In Words
1	24.76	KSRB 6-2.3 Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	cum	6609.18	Rupees Six Thousand Six Hundred Nine and Eighteen Paise Only
2	1.12	KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making laster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	cum	111196.94	Rupees One Hundred Eleven Thousand One Hundred Ninety Six and Ninety Four Paise Only
3	4.41	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures)	Sqm	4331.96	Rupees Four Thousand Three Hundred Thirty One and Ninety Six Paise Only
4	11.34	Providing and fixing in position Honne wood fully panelled shutters for windows with styles and rails of 35mm. thick, 75mm wide in two halves with panels of 25mm thick including cost of materials, labour charges, HOM of machineries complete	Sqm	5127.37	Rupees Five Thousand One Hundred Twenty Seven and Thirty Seven Paise Only
5	238.14	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications etc., complete with all leads and lifts as per the directions of the Enginee-in-charge of the work.	Kg	103.46	Rupees One Hundred Three and Forty Six Paise Only
6	0.81	KSRB 7.8 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28kg/m all duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows, not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and grinded electrically subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour charges and HOM of machinery complete as per specifications	Sqm	4022.69	Rupees Four Thousand Twenty Two and Sixty Nine Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

7	7.5	Providing lath plaster with cement mortar 1:3, 5cms thick with 6mm dia mild steel bars at 20 cms. c to c both horizontally and vertically fixing chicken mesh for drop chajja, facia, backing to cup boards including cost of all materials, labour, providing and removing form work HOM of machineries, curing, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	1016.8	Rupees One Thousand Sixteen and Eighty Paise Only
8	185.79	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete	Sqm	203.58	Rupees Two Hundred Three and Fifty Eight Paise Only
9	200.4	Providing 18mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Sqm	205.81	Rupees Two Hundred Five and Eighty One Paise Only
10	241.47	KSRB 15-3.4:- Providing 15mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete	Sqm	175.77	Rupees One Hundred Seventy Five and Seventy Seven Paise Only
11	386.19	KSRB 15.7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete	Sqm	28.92	Rupees Twenty Eight and Ninety Two Paise Only
12	386.19	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	68.97	Rupees Sixty Eight and Ninety Seven Paise Only
13	241.47	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. with primer	Sqm	83.44	Rupees Eighty Three and Forty Four Paise Only
14	37.8	KSRB15-17 : Painting of wood surface KSRB 15-17.1 : Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	33.37	Rupees Thirty Three and Thirty Seven Paise Only
15	37.8	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	86.77	Rupees Eighty Six and Seventy Seven Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

16	199.55	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete	Sqm	1249.3	Rupees One Thousand Two Hundred Forty Nine and Thirty Paise Only
17	29.4	KSRB 14.17,2: Providing skirting, dado, rises of steps with Colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications	Sqm	1047.95	Rupees One Thousand Forty Seven and Ninety Five Paise Only
18	20	Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 25mm dia nominal bore with fittings (medium grade weight 2.51kg/mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications	Rm	332.63	Rupees Three Hundred Thirty Two and Sixty Three Paise Only
19	2	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	No.	175.77	Rupees One Hundred Seventy Five and Seventy Seven Paise Only
20	2	Providing and fixing 7.5 cm to 15 cm dia NP grating 100 mm dia	No.	178.0	Rupees One Hundred Seventy Eight Only
21	72	Providing and fixing on wall surface 2.5kg / sq.cm H.D.P.E. rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, curing complete as per specifications.	Rm	528.42	Rupees Five Hundred Twenty Eight and Forty Two Paise Only
22	6	Providing and laying in position to required level or slope 100mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixutre of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges, complete as per specifications.	Rm	378.24	Rupees Three Hundred Seventy Eight and Twenty Four Paise Only
23	2	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity)	No.	9289.12	Rupees Nine Thousand Two Hundred Eighty Nine and Twelve Paise Only
24	1	2.0 HP / 1.5 kW submersible single phase pump	No.	29257.96	Rupees Twenty Nine Thousand Two Hundred Fifty Seven and Ninety
25	2	Providing fixtures - Door Lock	No.	420.85	Rupees Four Hundred Twenty and Eighty Five Paise Only
26	8	Providing fixtures - Handles power coated 150mm	No.	58.77	Rupees Fifty Eight and Seventy Seven Paise Only
27	16	Providing fixtures - Hinges 5" heavy duty	No.	38.83	Rupees Thirty Eight and Eighty Three Paise Only
28	4	Providing fixtures - Tower bolt 300 mm long	No.	121.74	Rupees One Hundred Twenty One and Seventy Four Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

29	1	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580x44mm with intergral type footrests, 100mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Each	2426.3	Rupees Two Thousand Four Hundred Twenty Six and Thirty Paise Only

K.V. Subba Reddy

Signature of the Contractor

Executive Engineer
Byaravanapura Division
BBMP, Bangalore - 92